BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 09

Name of Work:- Providing sign and ornamental boards in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Vijayakumar R	
				Rate	Rate in Words
1	Providing and fixing ornamental name boards of size 2.10 X 0.50Mtrs and column of size 0.15 x 0.15 Mtrs of height 1.23 Mtrs of each board made of C C 1:1, 5:3 with necessary centrering and form work smooth finishing with reinforcement etc including fabrication charges painting concreting and transportation charges from manufacturing yard to the site of work all lead and lift loadiing and undloading and labour charges etc. complete as per the direction of the engineer incharge of the work	Nos	2.00	5294.66	Rupees five thousand two hundred ninety four and paise sixty six only
2	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete.(P.No.65, I.No.8.04 of NH SR 2009-10) Supported on a class B GI pipe 80mm outer dia, 3.50mtr long 60cm x 60cm square	Sqm	196.00	4230.66	Rupees four thousand two hundred thirty and paise sixty six only
3	KSRRB 300-2. Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH chapter 3. No. 142/ Item No. 19.2(PWD SR 2016-2017)	Cum	0.80	97.66	Rupees ninety seven and paise sixty six only

1725919637829065 3/1725919637829065

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Vijayakumar R	
				Rate	Rate in Words
4	KSRRB 4.6 Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @0.53cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no 4.1,4.2 (Page.12 & Item No. 4.6)	Cum	0.90	4796.66	Rupees four thousand seven hundred ninety six and paise sixty six only
5	KSRRB M800-9: Painting new Kannada letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803,Page No. 184/ Item No. 24.9(PWD SR 2016-2017)	sqm	10840.00	0.66	paise sixty six only
6	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. (PWD SR 2016-2017)P.134/I.17.1)	Cum	0.80	61.66	Rupees sixty one and paise sixty six only

Vijaykumar.R
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

1725919637829065 3/1725919637829065